

A map with the exact location of road marked on it must be submitted with this road form.

REQUEST FOR ROAD IMPROVEMENT
HORRY COUNTY TRANSPORTATION COMMITTEE
Post Office Box 1236
Conway, South Carolina 29528
Telephone: (843) 915-5130 Fax: (843) 915-6130

Date: May 7, 2025

Road name or number: Legends Drive

Length of road: 2.42 Miles (12,800 LF)

Is this a public road owned by the county, state or municipality: Yes, Horry County

Who will do the roadwork: Contractor overseen by Horry County Engineering Dept.
(Will the county, state or municipality do the work or contract it out)

Number of homes on road: 1,200+ homes use Legends Dr for external access (single family homes and condos)

Is this a dead end road: No, not Legends Drive itself, but this road is the only external access for 1,200+ homes

Is this a school bus route: Yes

Has the required amount of right of way been dedicated to the County: Yes

Number of accidents that have occurred on this road recently: N/A

Contact person:

Name: Andy Markunas, County Engineer

Address: Horry County Government
4401 Privetts Rd
Conway, SC 29526

Phone #: 843-915-5160 (Work)

_____ (Home)

_____ (Cell)

markunaa@horrycountysc.gov (E-Mail)

Type of improvement requested:

☐ Coquina ☐ Pave ☒ Resurface ☐ Drainage ☒ Other

Comments: Horry County is requesting \$250,000.00 in funding from CTC for this project (11% of construction contract costs of \$2.21 M). In addition to repair and resurfacing work, the completed project will widen a short section of road to provide a center left turn lane (at the US 501 end), and wider shoulders will be built and paved along the remainder of the existing public road (2' shoulder widening on each side to improve safety). Please see the attachments for additional details (map, pay items w/ costs, etc.).



Legends Drive Schedule of Pay Items (May 2025, Horry CTC)					
Item #	Description	UOM	Unit Price	Quantity	Total Cost
1	Traffic Control (Includes Permanent Construction Signage) & Mobilization (Maximum Allowable Price to be 5% of Total Bid.	LS	\$ 110,000.00	1	\$ 110,000.00
2	Clearing/Grubbing within R/W	LS	\$ 90,000.00	1	\$ 90,000.00
3	Regrade/Relocate Roads or Ditches	Linear Foot/Feet	\$ 18.80	3,000	\$ 56,400.00
4	Unclassified Excavation (other)	Cubic Yard	\$ 50.05	500	\$ 25,025.00
5	Graded Aggregate Base Course - 8" Uniform (Include Fine Grading)	Square Yard	\$ 41.50	2,000	\$ 83,000.00
6	2" SCDOT HMA Type C Intermediate Course - New Lane	Tons	\$ 176.55	250	\$ 44,137.50
7	15" RC Pipe Cul. - Class III	Linear Foot/Feet	\$ 165.00	128	\$ 21,120.00
8	18" RC Pipe Cul. - Class III	Linear Foot/Feet	\$ 320.00	80	\$ 25,600.00
9	Variable Profile Milling	Square Yard	\$ 2.90	41,000	\$ 118,900.00
10	Full Depth Patching 8" SCDOT Intermediate	Square Yard	\$ 74.50	6,250	\$ 465,625.00
11	2' Widening (8" SCDOT Intermediate C)	Linear Foot/Feet	\$ 14.40	23,000	\$ 331,200.00
12	1.75" SCDOT HMA Type C Surface Course	Tons	\$ 128.30	4,400	\$ 564,520.00
13	Import Fill To Restore Grass Shoulders	Cubic Yard	\$ 35.20	3,000	\$ 105,600.00
14	4" Temporary Fast Dry Paint (Yellow, white, broken lines)	Linear Foot/Feet	\$ 0.10	80,200	\$ 8,020.00
15	24" Temporary Stop Bar	Linear Foot/Feet	\$ 1.00	100	\$ 100.00
16	Directional Arrow - Fast Dry Paint (15 mils wet)	Each	\$ 15.00	1	\$ 15.00
17	Combination Arrow - Fast Dry Paint (15 mils wet)	Each	\$ 15.00	1	\$ 15.00
18	4" Wide Thermoplastic (90 mils) (Yellow, white, broken lines)	Linear Foot/Feet	\$ 0.45	54,400	\$ 24,480.00
19	24" Stop Bar - Thermoplastic (125 mils)	Linear Foot/Feet	\$ 10.00	100	\$ 1,000.00
20	Directional Arrow - Thermoplastic (125 mils)	Each	\$ 150.00	1	\$ 150.00
21	Combination Arrow - Thermoplastic (125 mils wet)	Each	\$ 150.00	1	\$ 150.00
22	Permanent Pavement Markers (Bi-dir) Yellow and White	Each	\$ 5.00	350	\$ 1,750.00
23	Permanent Signage (stop, speed limit, etc)	Each	\$ 315.00	6	\$ 1,890.00
24	Sediment and Erosion Control	LS	\$ 20,000.00	1	\$ 20,000.00
25	Construction Staking / Surveying	LS	\$ 25,000.00	1	\$ 25,000.00
26	Shoulder Clipping	Linear Foot/Feet	\$ 0.25	25,600	\$ 6,400.00
27	Permanent Vegetation	ACRE	\$ 10,500.00	6	\$ 63,000.00
28	Muck and Replace Unsuitable material w/12" Graded Aggregate Base Course	SY	\$ 105.00	100	\$ 10,500.00
29	Removal of Existing RCP	LF	\$ 54.50	120	\$ 6,540.00
				Total	\$ 2,210,137.50